



- 1-LOAD-CELL (8 Pcs)
- 2-RAMP
- 3-MAIN BEAM (IPE 450)
- 4-TRAVERSE (IPE 270)
- 5-TRAVERSE (NPI 160)
- 6-COVERING SHEET (10mm)

FOR FOUNDATION ;
 VOLUME OF EXCAVATION: 83m³
 VOLUME OF CONCRETE : 33³
 REINFORCEMENT STEEL : 1558 kg

Code	Capacity(kg)	Dimension(m)	Platform	Loadcell	Weight(kg)
060T-JU-S-0314	60000	3x14	Steel	SC (8 Pcs)	9500

DRAWN BY: B.ÇINAR			www.esitscale.com							
CONTROL : V.AKGÜN			DESCRIPTION							
REVISION		DATE	BRAND : ESİT							
A	B	C	D	E	F	G	18/09/2008	MODEL : 3x14m 60t JUMBO-S Truck Scale		