


- 1-LOAD-CELL (8 Pcs)
- 2-RAMP
- 3-MAIN BEAM (IPE 450)
- 4-TRAVERSE (IPE 270)
- 5-TRAVERSE (NPI 160)
- 6-COVERING SHEET (10mm)

FOR FOUNDATION ;
 VOLUME OF EXCAVATION: 97m³
 VOLUME OF CONCRETE : 35³
 REINFORCEMENT STEEL : 1651 kg

Code	Capacity(kg)	Dimension(m)	Platform	Loadcell	Weight(kg)				
060T-JU-S-0318	60000	3x18	Steel	SC (8 Pcs)	12000				
DRAWN BY: B.ÇINAR				www.esitscale.com					
CONTROL : V.AKGÜN									
REVISION		DATE		DESCRIPTION					
A	B	C	D	E	F	G	18/09/2008	BRAND : ESİT	
								MODEL : 3x18m 60t JUMBO-S Truck Scale	