



- 1-LOAD-CELL (10 Pcs)
- 2-RAMP
- 3-MAIN BEAM (IPE 450)
- 4-TRAVERSE (IPE 270)
- 5-TRAVERSE (NPI 160)
- 6-COVERING SHEET (10mm)

FOR FOUNDATION ;  
 VOLUME OF EXCAVATION: 104m<sup>3</sup>  
 VOLUME OF CONCRETE : 38<sup>3</sup>  
 REINFORCEMENT STEEL : 1840 kg

Code	Capacity(kg)	Dimension(m)	Platform	Loadcell	Weight(kg)
060T-JU-S-0320	60000	3x20	Steel	SC (10 Pcs)	13400

DRAWN BY: B.ÇINAR

CONTROL : V.AKGÜN

REVISION

DATE

A B C D E F G 18/09/2008

**ESİTİ**<sup>®</sup>  
LTD.

[www.esitscale.com](http://www.esitscale.com)

DESCRIPTION

BRAND : ESİTİ

MODEL : 3x20m 60t JUMBO-S Truck Scale