


- 1-LOAD-CELL (4 Pcs)
- 2-MAIN BEAM (IPE 450)
- 3-TRAVERSE (NPI 160)
- 4-TRAVERSE (NPI 200)
- 5-COVERING SHEET (10mm)

FOR FOUNDATION ;
 VOLUME OF EXCAVATION: 53m³
 VOLUME OF CONCRETE : 20m³
 REINFORCEMENT STEEL : 1085 kg

Code	Capacity(kg)	Dimension(m)	Platform	Loadcell	Weight(kg)
040T-DI-0306	40000	3x6	Steel	SC (4 Pcs)	3950
DRAWN BY: B.ÇINAR				www.esitscale.com	
CONTROL : V.AKGÜN					
REVISION		DATE		DESCRIPTION BRAND : ESİT MODEL : 3x6m 40t DINO Truck Scale	
<input checked="" type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D <input type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G	10/05/2007				