


- 1-LOAD-CELL (6 Pcs)
- 2-MAIN BEAM (IPE 450)
- 3-TRAVERSE (NPI 160)
- 4-TRAVERSE (NPI 200)
- 5-COVERING SHEET (10mm)

FOR FOUNDATION ;
 VOLUME OF EXCAVATION: 68m³
 VOLUME OF CONCRETE : 26³
 REINFORCEMENT STEEL : 1368 kg

Code	Capacity(kg)	Dimension(m)	Platform	Loadcell	Weight(kg)
040T-DI-0308	40000	3x8	Steel	SC (6 Pcs)	5400
DRAWN BY: B.ÇINAR				www.esitscale.com	
CONTROL : V.AKGÜN					
REVISION		DATE		DESCRIPTION	
<input checked="" type="checkbox"/>	B C D E F G	10/05/2007		BRAND : ESİT	
MODEL : 3x8m 40t DINO Truck Scale					