


- 1-LOAD-CELL (6 Pcs)
- 2-MAIN BEAM (IPE 450)
- 3-TRAVERSE (NPI 160)
- 4-TRAVERSE (NPI 200)
- 5-COVERING SHEET (10mm)

FOR FOUNDATION ;
 VOLUME OF EXCAVATION: 68m³
 VOLUME OF CONCRETE : 26m³
 REINFORCEMENT STEEL : 1368 kg

Code	Capacity(kg)	Dimension(m)	Platform	Loadcell	Weight(kg)				
060T-DI-0308	60000	3x8	Steel	SC (6 Pcs)	5400				
DRAWN BY: B.ÇINAR				www.esitscale.com					
CONTROL : V.AKGÜN									
REVISION		DATE		DESCRIPTION					
<input checked="" type="checkbox"/>	B	C	D	E	F	G	10/05/2007	BRAND : ESİT MODEL : 3x8m 60t DINO Truck Scale	