


- 1-LOAD-CELL (8 Pcs)
- 2-MAIN BEAM (IPE 450)
- 3-TRAVERSE (NPI 160)
- 4-TRAVERSE (NPI 200)
- 5-COVERING SHEET (10mm)

FOR FOUNDATION ;  
 VOLUME OF EXCAVATION: 146m<sup>3</sup>  
 VOLUME OF CONCRETE : 46m<sup>3</sup>  
 REINFORCEMENT STEEL : 2395 kg

Code	Capacity(kg)	Dimension(m)	Platform	Loadcell	Weight(kg)				
060T-DI-0318	60000	3x18	Steel	SC (8 Pcs)	11450				
DRAWN BY: B.ÇINAR				<a href="http://www.esitscale.com">www.esitscale.com</a>					
CONTROL : V.AKGÜN									
REVISION		DATE		DESCRIPTION					
<input checked="" type="checkbox"/>	B	C	D	E	F	G	10/05/2007	BRAND : ESİT MODEL : 3x18m 60t DINO Truck Scale	