


- 1-LOAD-CELL (8 Pcs)
- 2-MAIN BEAM (IPE 550)
- 3-TRAVERSE (NPI 200)
- 4-TRAVERSE (NPI 200)
- 5-COVERING SHEET (10mm)

FOR FOUNDATION ;
 VOLUME OF EXCAVATION: 130m³
 VOLUME OF CONCRETE : 41m³
 REINFORCEMENT STEEL : 2188 kg

| Code | Capacity(kg) | Dimension(m) | Platform | Loadcell | Weight(kg) | | | | |
|-------------------------------------|--------------|---|----------|--|------------|---|------------|--------------|--|
| 100T-DI-0316 | 100000 | 3x16 | Steel | SC (8 Pcs) | 12450 | | | | |
| DRAWN BY: B.ÇINAR | |  | | www.esitscale.com | | | | | |
| CONTROL : V.AKGÜN | | | | | | | | | |
| REVISION | | DATE | | DESCRIPTION | | | | | |
| <input checked="" type="checkbox"/> | B | C | D | E | F | G | 10/05/2007 | BRAND : ESİT | |
| MODEL : 3x16m 100t DINO Truck Scale | | | | | | | | | |