


- 1-LOAD-CELL (8 Pcs)
- 2-MAIN BEAM (IPE 550)
- 3-TRAVERSE (NPI 200)
- 4-TRAVERSE (NPI 200)
- 5-COVERING SHEET (10mm)

FOR FOUNDATION ;  
 VOLUME OF EXCAVATION: 146m<sup>3</sup>  
 VOLUME OF CONCRETE : 45m<sup>3</sup>  
 REINFORCEMENT STEEL : 2375 kg

Code	Capacity(kg)	Dimension(m)	Platform	Loadcell	Weight(kg)				
100T-DI-0318	100000	3x18	Steel	SC (8 Pcs)	13850				
DRAWN BY: B.ÇINAR				<a href="http://www.esitscale.com">www.esitscale.com</a>					
CONTROL : V.AKGÜN									
REVISION		DATE		DESCRIPTION					
<input checked="" type="checkbox"/>	B	C	D	E	F	G	10/05/2007	BRAND : ESİT MODEL : 3x18m 100t DINO Truck Scale	