


- 1-LOAD-CELL (6 Pcs)
- 2-RAMP
- 3-BEAM
- 4-COVERING SHEET (10mm)

FOR FOUNDATION:

VOLUME OF EXCAVATION : 56m³
 VOLUME OF CONCRETE : 22m³
 REINFORCEMENT STEEL : 945 kg

Model	Capacity(kg)	Dimension(m)	Platform	Loadcell	Weight(kg) ± %2		
060T-HI-S-0308	60000	3x8	Steel	SC (6 Pcs)	5250		
DRAWN BY: B.ÇINAR				www.esitscale.com			
CONTROL : V.AKGÜN							
REVISION		DATE		DESCRIPTION BRAND: ESİT MODEL : 3x8m 60t HIPPO-S Truck Scale			
A	B	C	D			E	F