


- 1-LOAD-CELL (8 Pcs)
- 2-RAMP
- 3-BEAM
- 4-COVERING SHEET (10mm)

FOR FOUNDATION:

VOLUME OF EXCAVATION : 86m³
 VOLUME OF CONCRETE : 26m³
 REINFORCEMENT STEEL : 1356 kg

Model	Capacity(kg)	Dimension(m)	Platform	Loadcell	Weight(kg) ± %2				
060T-HI-S-0318	60000	3x18	Steel	SC (8 Pcs)	10200				
DRAWN BY:Ş.AYDIN		 www.esitscale.com							
CONTROL :V.AKGÜN									
REVISION		DATE		DESCRIPTION					
A	B	C	D	E	F	G	22/04/2009	BRAND:ESİT	
MODEL :3x18m 60t HIPPO-S Truck Scale									