


- 1-LOAD-CELL (10 Pcs)
- 2-RAMP
- 3-BEAM
- 4-COVERING SHEET (10mm)

FOR FOUNDATION:

VOLUME OF EXCAVATION : 100m³
 VOLUME OF CONCRETE : 29m³
 REINFORCEMENT STEEL : 1520 kg

| Model | Capacity(kg) | Dimension(m) | Platform | Loadcell | Weight(kg) ± %2 | | | | |
|--------------------------------------|--------------|---|----------|--|-----------------|---|------------|------------|--|
| 060T-HI-S-0322 | 60000 | 3x22 | Steel | SC (10 Pcs) | 12650 | | | | |
| DRAWN BY:Ş.AYDIN | |  | | www.esitscale.com | | | | | |
| CONTROL :V.AKGÜN | | | | | | | | | |
| REVISION | | DATE | | DESCRIPTION | | | | | |
| A | B | C | D | E | F | G | 22/04/2009 | BRAND:ESİT | |
| MODEL :3x22m 60t HIPPO-S Truck Scale | | | | | | | | | |